

Orchard 2013 Timber Sale

Additional Question and Response

June 25, 2013

Q. What are the mulch requirements at map point #2?

A. Straw shall be spread 18" deep along the newly excavated channel banks where the 30' of perched filled has been removed (refer to THP page 40, figure 3). The balance of the exposed soil within the WLPZ shall be mulched with straw or slash with at least 95% cover with a minimum depth of 4".